

ARIZONA DEPARTMENT OF TRANSPORTATION

REPORT NUMBER: FHWA-AZ88-204

EVALUATION OF COMPUTER-AIDED DRAFTING AND DESIGN CAPABILITIES IN THE HIGHWAY DEVELOPMENT ENVIRONMENT

Final Report

Prepared by:
William A. Wakefield
Robert T. Trujillo
Highway Plan Services
Arizona Department of Transportation
206 South 17th Avenue
Phoenix, Arizona 85007

April 1988

Prepared for:
Arizona Department of Transportation
206 South 17th Avenue
Phoenix, Arizona 85007
in cooperation with
U.S. Department of Transportation
Federal Highway Administration

The contents of this report reflect the views of the authors who are responsible for the facts and the accuracy of the data presented herein. The contents do not necessarily reflect the official views or policies of the Arizona Department of Transportation or the Federal Highways Administration. This report does not constitute a standard, specification, or regulation. Trade or manufacturer's names which may appear herein are cited only because they are considered essential to the objectives of the report. The U.S. Government and the State of Arizona do not endorse products or manufacturers.

TECHNICAL REPORT DOCUMENTATION PAGE

1. REPORT NO.	2. GOVERNMENT ACCESSION NO.	3. RECIPIENT'S CATALOG NO.
FHWA-AZ88-204		

4. TITLE AND SUBTITLE

EVALUATION OF COMPUTER-AIDED DRAFTING AND DESIGN CAPABILITIES IN THE HIGHWAY DEVELOPMENT ENVIRONMENT

5. REPORT DATE
April 1988

6. PERFORMING ORGANIZATION CODE

7. AUTHOR(S)
William A. Wakefield
Robert T. Trujillo

8. PERFORMING ORGANIZATION REPORT NO.

9. PERFORMING ORGANIZATION NAME AND ADDRESS
Highway Plan Services
Arizona Department of Transportation
206 South 17th Avenue
Phoenix, Arizona 85007

10. WORK UNIT NO.

11. CONTRACT OR GRANT NO.
HPR-PL-1(31) ITEM 204

12. SPONSORING AGENCY NAME AND ADDRESS
ARIZONA DEPARTMENT OF TRANSPORTATION
206 S. 17TH AVENUE
PHOENIX, ARIZONA 85007

13. TYPE OF REPORT & PERIOD COVERED
Final Report
May 1983 - April 1988

14. SPONSORING AGENCY CODE

15. SUPPLEMENTARY NOTES

Prepared in cooperation with the U.S. Department of Transportation, Federal Highway Administration

16. ABSTRACT

Significantly expanded highway construction and rehabilitation programs by the Arizona Department of Transportation resulted in an increase of design work load within the Highway Development group. Improvements in design and drafting production were attempted through the use of Computer Aided Drafting and Design (CADD) system. Originally the hardware and software for a small standalone CADD system with one work station was installed in order to evaluate the effectiveness of the system. The TERAK CADD system submitted by BFA Corporation was chosen for testing.

Initial studies concluded that the TERAK CADD system did not have the hardware that had the capability nor the software available to effectively prepare most highway construction plan sheets. The types of plan sheets that were evaluated along with other types of drafting functions that were conducted are described in the report.

During the early stages of the project a decision was made by the Department to purchase and install a major CADD system which would have the capabilities of serving the entire organization. The decision to purchase a major CADD system was based on the technology in use by various Departments of Transportation across the nation.

The study has concluded that a CADD system with proper hardware and software has an unlimited potential to reduce the cost and time in preparing plan sheets. However, the cost of such a CADD system is much greater than the amount that was budgeted for this project.

17. KEY WORDS	18. DISTRIBUTION STATEMENT
Computer Aided Drafting and Design System, Highway Plans, Drafting Functions, System Requirements, Drafting Equipment	Document is available to the U.S. public through the National Technical Information Service, Springfield, Virginia 22161

19. SECURITY CLASSIF. (of this report)	20. SECURITY CLASSIF. (of this page)	21. NO. OF PAGES	22. PRICE
Unclassified	Unclassified	27	

TABLE OF CONTENTS

LIST OF FIGURES

INTRODUCTION

Throughout the past several years, the Arizona Department of Transportation has pursued an energetic and significantly expanded highway construction and rehabilitation program for improving highway transportation throughout the state. This expanded program resulted in an increase of design work load within the Highway Development Group and, in particular, Highway Plans Services.

With this increase of design work load, it became apparent that some action to increase production capacity was required, in particular an increase in drafting capacity. Research of the Engineering Consultant profession and other state agencies showed that improvements in drafting production could be accomplished through the use of Computer Aided Drafting and Design (CADD) rather than increases in personnel. In regards to drafting production, this research also indicated that the trend within the engineering field was toward a tremendous increase in the use of CADD.

CADD is a new concept of using computers to do the drafting and design. The concept is called interactive computerized graphics design. When an engineer/technician feeds the data for a design into a computer, the response he gets on the screen is a drawing of his design. The CADD equipment being used by the engineer/technician has the ability to graphically represent the design on the screen almost instantaneously.

In addition to getting the final design produced quicker, interactive graphics also provide the potential for a better design than before. The process allows an engineer/technician to develop numerous design approaches to any particular project. Once the design data is entered into a CADD system, additions, modifications, or deletions can be made very easily.

By mid-1983, a research project involving evaluation of a Computer Aided Drafting and Design system had been proposed and approved.

In October of 1983, the vendor's proposal for a CADD system was accepted and the system was delivered in January of 1984.

OBJECTIVES

The original objective of this research project was to determine if Highway Plans Services would benefit by converting to a computerized method of completing the Highway Design process, and to provide a recommendation on the future use of CADD in the design process within the Highway Development environment. The hardware and software for a small standalone CADD system with one work station was installed to provide Highway Plans design staff the use of the CADD in order to evaluate the effectiveness of the system in regards to equipment and usage procedures.

Investigation of various drafting applications was to find out which methods would prove to be more productive through utilization of the CADD system. An important part of this study was to determine the level of training that would be required.

During the early stages of the project a decision was made by the Department to purchase and install a major CADD system which would have the capabilities of serving the entire organization within the next two years. The new major CADD system would have the capabilities of networking all the CADD users together within the same system, thereby, making it possible for users from different services to transfer and exchange drawings very quickly and efficiently. The decision to purchase a major CADD system was based on the technology in use by various other Departments of Transportation in the United States. Consideration was given to proposed change in work load, work/service measurements, benefits (such as reduction in drafting costs, increase in productivity, and decrease in staff size), impact of not funding such a system, and capital outlay.

The decision to purchase a major CADD system together with the initial findings that the small standalone CADD system did not appear to have the capabilities in either the hardware or the software to efficiently develop the majority of the plan sheets required in a typical highway project prompted a re-evaluation and revision in the original scope of the research project.

The new direction of the research project was to use the small standalone CADD system to teach potential future users of the major CADD system how a CADD system operates and how it can be used to create the various types of drawings that are necessary to prepare a set of highway construction plans. A small group of Highway Plans design personnel were selected and two-person teams were formed to work with the CADD equipment.

Training sessions were conducted for each team to familiarize them with the basics of CADD software and hardware. Each team was allotted a minimum amount of CADD time each week and allowed to progress at their own individual pace. Because of the software and hardware limitations discovered during the initial testing of the system, the use of the CADD system was restricted to Overlay projects, typical section and detail sheets.

The system was also to be used to gauge the level of training that the users require to become proficient in the use of the system. Training and usage of the system was to be restricted to those ideas, methods and software commands that appear to be able to be transferred over to the new major CADD system. The new objective was to familiarize as many people as possible in the processes of a CADD system.

The standalone CADD system was also to be used to supplement any special drafting functions (Awards, forms, standards, etc.) being performed by Highway Plans Services personnel.

DESCRIPTION OF WORK COVERED UNDER THIS RESEARCH PROJECT

The plans to be prepared using the standalone CADD system for highway construction along with the specifications are the final result of the preliminary planning and survey of the area. They show the extent to which the design requirements are to be carried out and, above all, they constitute the documents on which a contractor is expected to figure his bid price and to construct a finished road. They also must be reviewed and thoroughly understood by the approving authority of the state and other organizations involved in building the road. Therefore, the plans should be completely and accurately drawn.

A typical full set of plans for an Urban or Rural highway consist of the following:

1. The Face Sheet:

   The Face Sheet includes the name and number of the project along with a vicinity map showing the location of the project with provision in the lower right corner for FHWA and Departmental approval signatures.

2. The list of Standards Sheets:

   These sheets list all applicable roadway Standard Drawings - Construction Details by number, name, and latest revision date.

3. The Design Sheet:

   This sheet shows length of project, index of sheets, general notes, present and design ADT, design speed, and a fully-dimensioned typical roadway cross-section and pavement structure composition. If required, tables are used to show location of changes in pavement structure composition thicknesses, cut ditch dimensions, cut and embankment slopes, and earthwork quantity summaries.

4. The Detail Sheet:

   This sheet provides construction drawings of all miscellaneous, nonstandard items not covered in the Standard Drawing - Construction Details.

5. The Quantity Summary Sheet:

   This sheet lists summarized quantities, dimensional specifications for all drainage-related items and guard rail-related items.

6. The Plan and Profile Sheet:

   This sheet shows the centerline of construction, with the bearing of tangents, stations of beginning and ending of curves, curve data, and station points; the right of way, and all existing detail drawn with dash lines. Also shown are the edges of the new road, new culverts and bridges, and all special features such as guard rail, retaining walls, turnouts, drainage, and all related notes.

7. Structural Sheet:

   This sheet is prepared by the Structures Section and provides all details of the structures on the project.

8. Traffic Sheet:

   This sheet is prepared by the Traffic Engineering Section and provides all details concerned with signing, lighting, traffic control, and delineation.

9. Roadside Development Sheet:

   This sheet is prepared by Roadside Development Services and provides all details concerned with landscaping, landscaping irrigation, rest areas, and other roadside beautification facilities.

10. Material Sheet:

    This sheet is prepared by Material Section and comprise:

    A. Sketch maps of borrow and aggregate sources.

    B. Test results for borrow and aggregate sources.

    C. Subgrade information and soil profile.

A typical full set of plans for an Overlay project consists of the following:

1. The Face Sheet.
2. The list of Standards Sheets.
3. The Design Sheet.
4. Material Sheets.

CADD SYSTEM REQUIREMENTS

The system to be acquired needs to satisfy the following minimum requirements:

A. The equipment should stand alone and be located in and operated by Highway Plans Services.

B. The software should offer security, not require a programmer for service, be capable of layering, accept some customizing, preferably accept other engineering oriented software and be user oriented.

C. The plotter should accept various paper sizes through "D" size plan sheets, operate with various sizes of ink pen line widths and pen qualities.

D. All of the equipment should operate on the normal 110 volt system and in the normal office environment.

E. The preferable system should offer ease of use, data base intelligence, associativity between graphic and non-graphic descriptive information, if possible third level software, drafting functionality to permit defining ADOT graphic symbols and quantitative calculations from the drawings.

SELECTION PROCESS FOR THE STANDALONE CADD SYSTEM

An invitation for bid was issued for the purpose of receiving cost quotations and technical proposals for a two-dimensional (2D) computer aided drafting and design (CADD) system for civil engineering applications.

The packages submitted by the vendors were analyzed and the handling capability of each software was rated using the following standards: Level I was considered to be below standard, its capabilities falling below the majority of the systems studied. Level II was average, its capabilities exceeding those of Level I but not those of Level III. Level III was above standard, its capabilities exceeding both Levels I and II. The performances of some of the hardware software combinations were observed and the documentation provided by the vendors was reviewed whenever demonstrations could not be provided .

One of the requirements of the system was that it be capable of driving a full "D" size engineering oriented plotter. Most observed systems used a Hewlett-Packard Model 7580A or were compatible with that plotter. In searching for the desired plotter, no other plotter could compete in price and quality with the ability to draw complete "D" size plan sheets.

The following is a brief description of the systems that the vendors submitted in response to the invitation for bid and subsequently were given consideration in the awarding of the contract:

The first package studied was CEADS provided by Holquin & Associates Inc. of El Paso, Texas. The price of the total package was $13,500 and operated on a Hewlett Packard Computer. The software rated at Level I.

The research included a Design Oriented Graphics system (DOGS) developed by PAEC in England. They have a representative in Knoxville, Tennessee. This CADD system is around Level III. It runs on Prime, Data General, VAX (DEC), Harris, Perkin-Elmer, Apollo and requires a minimum of 1 meg floppy disk, 20 meg fixed disk and 512 RAM. This software cost $20,000 for 1 user,

$30,000 for two users, and then $300 for each additional user thereafter.

A system by General Drafting systems (GDS) was also researched. This system was developed by Applied Research of Cambridge in England. GDS is a Level III software package that is available from McAuto. The price range was comparable to Design Oriented Graphics system (DOGS).

The studies included a system named MEDUSA that appeared to be an enhanced GDS. MEDUSA will only operate on a Prime Computer. The MEDUSA software cost $35,000, Prime Computer 2250 with a PW 200 Work Station cost $16,000, and the Hewlett Packard Model 7580A Plotter cost $16,000, giving the total package cost of $77,000.

The last system studied was the TERAK CADD system submitted by BFA Corporation from Scottsdale, Arizona. The components of the TERAK CADD system are listed in Figure 1. Figures 2, 3, and 4 illustrate some of the major components of the system. The software was rated at Level III. The price on their system including both hardware and software was $71,000.

The proposal submitted by BFA Corporation which consisted of the TERAK CADD system was rated the best overall and was selected. The TERAK CADD system was the only system that was able to provide local support for both the hardware and software which was a major consideration in making the final selection.

TERAK Model 8600B-23DGA Color Design Graphics system includes:

1. LSI 11/23 (16 bit microprocessor).
2. 128K bytes of memory.
3. Two floppy disk drives (2.4 megabytes total).
4. Quad RS232 serial interface.
5. 320x240 monochrome monitor.
6. 4601-19LFI 19" color monitor.
7. Keyboard.
8. GTCO Corporation DIGI-PAD 11"x11" digitizes tablet with one button puck.
9. Hewlett Packard HP7580B "D" Size Plotter.
10. 8518B-40WA Winchester Technology Hard Disk with 40M byte informatus storage capacity.
11. #84864 Mode Powermaker Topaz Uninterruptible Power system.
12. Programmable Design Graphix software.
13. DG-COGO Software Package.
14. OKIDATA MICROLINE 192 Printer

FIGURE 1 - TERAK CADD SYSTEM COMPONENT LISTING



Figure 2 - TERAK PROCESSOR, MONITOR AND KEYBOARD



Figure 3 - COMPONENTS - 851B WINCHESTER DISK DRIVE ASSEMBLY